BRUHAT BANGALORE MAHANAGARA PALIKE

Office of the Executive Engineer, Rajarajeshwari Nagara Division, RR Nagara Zone, B.B.M.P., Bangalore.

Tender Notification No: EE/RRND/Tend/13/2018-19 Date: 27.02.2019

Indet No: BBMP/2018-19/OW/WORK_INDENT34926

SCHEDULE -B

Name of Work: Annual maintenance of Cremotorium Burial Ground and office maintenance in Jalahalli ward no 16

Sl.No	Qty	Description of work	Unit	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	1200.20	Earthwork in surface excavation in ordinary soil for leveling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed as per specifications	Cum	258.00	Rupees Two Hundred Fifty Eight Only
2	1200.20	Loading and Unloading of Stone Boulder / Stone aggregates /Sand/ Kanker / Moorum. KSRRB M100-1 : Placing tipper at loading point, loading with front end loader,dumping, turning for return trip, excluding time for haulage and return trip complete as per specifcations.	Cum	100.00	Rupees One Hundred Only

Signature of the Contractor

Executive Engineer
RRNagara Division
BBMP